



Wilderness Collection Material List

Log Wall System

Milled 4"x 6" D-shaped Cedar Logs
Oly Log Screws
Spray Foam Insulation
Caulking
4x6 Bracing where Required

First Floor System*

2x Built up Girder
2x Rim Joists
2x Floor Joists/Blocking
5/8" Sub Floor Sheathing (OSB)

Interior Wall Framing

2x4/2x6 Top and Bottom Plates
2x4/2x6 Studs and Blocking
4x8/6x8 Header stock where Required
T&G Pine Sheathing for all Interior Partitions
1x Pine Trim

Loft/Second Floor System

2x Floor Joists
5/8" Sub Floor Sheathing (OSB)
3/4" T&G Pine Ceiling

Roof System

2x Rafters or Premanufactured Trusses
5/8" Roof Sheathing (OSB)
3/4" T&G Pine Ceiling
15 lb Felt Paper
25 yr 3 Tab Shingles
Galv. Drip Edge
1x Pine Facia/Freeze Board

Deck/Porch

2x Pressure Treated Framing
5/4" Cedar Decking
2x Rafters or Premanufactured Trusses
6x6 Porch Posts

Door Package

Pre Hung Fiberglass Exterior Doors w/locksets
1x Cedar Exterior Trim
6 Panel Pine Interior Doors
1x Pine Interior Trim

Window Package

200 Series Andersen Windows (no grills)

* Cabins designed to be supported with timber framed sills and posts to grade.